

Project Profile

Pacific Gas and Electric Materials Center and Distribution Yard
Fresno, CA
Constructed: July – October 2012

Scope of Work:

Owner needed to replace failing asphalt pavement. Heavy loads, equipment and coils of wire are stored in this yard and must be accessible year around. The yard had to remain open during reconstruction.

Design Factors:

Remove failing 7.5 inches asphalt
Re-grade sub-base.
Place 7.5 inches concrete pavement

Concrete:

8 laser screed pours for a total of 8600 cy
2 pours a month during July – October
2012.

Contractor:

Airport Specialty Products
Owner- Rob Karam
Office 559-439-9738



Before



After